

Upgrading the Reactor Power Control Concept with a Modern Digital Control System

M. Längle, R. Schildheuer

TÜV SÜD Energietechnik GmbH Baden-Württemberg Mannheim, Germany

Overview



- Plant History
- Reasons for Retrofitting
- Structure of the Reactor Power I&C System
- Phase Plan for Project Execution
- System Engineering
- Quality-assurance Measures
- Preparatory Infrastructural Measures
- Commissioning of the Digital Control System
- Conclusion

Plant History





- Pressurized-water reactor of the 2nd generation
- Pre-convoy series
- Erection starts in July 1977
- Commercial operation since April 1985
- Electrical nominal gross output approx.1450 MW

- Retrofitting the Reactor Power I&C System as well as the In-Core Neutron Flux Measuring System



Reasons for Retrofitting

- Optimization of the plant's operational performance
- Improving the procedures in the event of disturbances or failures
- Better identification of abnormal operating states
- Optimization of the reactor power I&C messages and displays
 - Increasing the plant's reliability, safety and availability
- Facilitation in future repair procedures / spare parts deliveries
- Upgrade the plant to the latest state of the art
 - Modern and type-tested digital control system for safety I&C applications





Structure of the Reactor Power I&C System (single redundancy)

Control Process variables \otimes ($\mathcal{F} \otimes$ room Switchgear building Conventional annunciation Recording/ Recording/ system Processing Processing In-Core Voter Measuring Monitoring & Service Interface FO FO FO system Limitation Limitation system system MSI MSI Switch Gateway FO = Fibre Optics Plant process Switch computer Gateway Drives Reactor contro Switch Voter Voter systems MSI MSI Emergency building MSI Service Unit Drives Control rod groups **Drives**



Structure of the Reactor Power I&C System (all redundancy levels)

Control Process variables $\otimes \land \otimes$ room Switchgear building Conventional annunciation Recording/ Recording/ system Processing Processing In-Core 1000 Voter Measuring Monitoring & Service Interface FO FO FO system Limitation Limitation system system MSI MSI Switch Gateway FO = Fibre Optics Plant process Switch computer Gateway **Drives** Reactor contro Voter Voter systems MSI MSI Emergency building MSI Service Unit Drives Control rod groups **Drives**



Phase Plan for Project Execution



- Phase plan structures the project activities
- Phase plan provides for a transparent and quality-assured implementation of the entire project

Energietechnik

Energietechnik

System Engineering



- System engineering by using tool system SPACE
 - SPecification <u>And</u> <u>Coding</u> <u>Environment</u>
- Provides graphic editor, code generators and testing tools
- Generates a consistent specification
- Generates executable programmes automatically

SIVAT (Simulation & Validation Tool)



- SIVAT provides a simulation environment for the control system
- Discrete tests on the engineered control functions after the code generation
- Generating the test specifications on basis of the function charts
- Simulation run based on test scripts
 - Identifying and elimination of project engineering errors at an early phase



REDIFF (Redundancy-Comparison-Tool)



- REDIFF provides a redundancy comparison tool
- Checking the redundant function charts for consistency
- Shows the discrepancies between redundant function charts
 - Identifying and elimination of project engineering errors at an early phase

Quality-assurance Measures (ATHLET)





- Simulator program ATHLET enables computer-aided modeling of
 - reactor protection functions
 - limitation functions
 - major control functions
 - Examination and recalculation of transient trends
 - 35 Transient trends examined

- Result of the examination:
 - The changes in the reactor power I&C system functions fulfilled the criteria defined in the Reactor Safety Commission guidelines

Quality-assurance Measures (Plant Simulator)





- Adaptations on the plant simulator in the test center in Essen
 - system and peripheral specific
- Integral test of the interactions between the control functions by simulating the process variables
- Simulations included the performance of plant transients

- Result of the Simulations :
 - Verifying of the specified functions and the improvements made for an operational plant optimization
 - Transferring specific know-how to the on-plant personnel

Preparatory Infrastructural Measures (Plant Process Computer)



- Preceding project to replace the plant process computer
 - Integration of the existing single-computer systems into a redundant high-performance and consistent plant process computer
 - Optimization of the human-machine-interface by modern on-screen-based operating and visualizing techniques as well as the control room design



Preparatory Infrastructural Measures (Power Supply System)



- Identifying the power and space requirements of the new reactor power I&C system
- > Preparation of the battery rooms for an increase in capacity
- Installation of switch bays with additional outgoing circuits and a discharge inverter for the batteries







Energietechnik

Preparatory Infrastructural Measures (Marshalling Cabinets)



- Marshalling cabinets with two terminal sides (system connection side, plant connection side) which are linked via planned transverse connections (TC)
- Connecting the system cables of the digital control system to the system connection side already after the installation of the control cabinets
 - Signal-specific preliminary tests (cold tests) independent of the overhaul activities
 - Detecting and elimination of wiring errors prior to the overhaul activities
 - More time for the remaining overhaul activities



Commissioning of the Digital Control System



- Commissioning of the entire system in step by step
- I&C commissioning tests \rightarrow process-specific commissioning tests
- Consistent documentation of the commissioning procedure
- Tests in the presence of the officially appointed inspector
 - Quality assured procedure to ensure the specified control and process-specific functionality



Conclusion

- Project execution on basis of a phase plan
- Documentation along with the phase-specific tests
- Preparatory infrastructural measures
- Consistent using of quality assurance measures
- Participation of the officially appointed inspector "TÜV SÜD Energietechnik"
 - Performing a fluently commissioning procedure on the plant
 - Despite the large volume of replacement work successfully retrofitting of the reactor power I&C system without causing a relevant extension of a periodic plant standstill
 - Fulfillment of the stringent quality requirements applicable to such a complex system

IAEA-Conference Vienna 03.11.2009 17







Energietechnik

Thank you for your attention!

